"Saguramo-navtlugi" Gas main pipeline construction project Section 10-20km LOT #1

Bill of Quantities

N⁰	Type of Activity	Unit	Quantity	Price	
1	Transportation of pipes and other fittings to the con-	nstruction site			
1,1	Transportation of JH1200 non coated pipes	km	0,228		
1,2	Transportation of ДН720×14 coated pipes	km	0,0635		
1,3	Transportation of ДН720×10 coated pipes	km	10,493		
1,4	Transportation of ДН219×6 coated pipes	km	0,065		
1,5	Transportation of ДН159×6 coated pipes	km	0,081		
1,6	Transportation of μ H89×5 coated pipes	km 1	0,360		
1,7	Transportation of Lends and other fittings	km	0,035		
1,0	Transportation of bends and other fittings	unit	40		
2	ROW Preparation				
2,1	Topsoil stripping	km	10,603		
2,2	Shell cutting and KOW leveling (as per design drawings)	km unit	1,/583		
3	bending	unit	120		
4	Trenching				
4,1	Trench preparation for D=700mm pipeline section	km	10,603		
4,2	Trench preparation for D=219mm pipeline section	km	0,065		
4,3	Trench preparation for D=150mm pipeline section	km	0,081		
5	Welding				
5,1	Welding of D1200 non-coated pipes	km	0,228		
5,2	Welding of D720×14 coated pipes	km	0,0635		
5.3	Welding of D720×10 coated nines	km	10 493		
5.4	Welding of D219×6 coated pipes	km	0.065		
5.5	Welding of D159×6 Coated pipes	km	0.081		
5,6	Welding of D89×5 Coated pipes	km	0,360		
5,7	Welding of D700mm Hotbends	unit	32		
5,8	Welding of fittings: (Tee 720x325-2units, Tee 159x6-1unit, Tee 219x8-1unit, Adaptor 325x159-1unit, Adaptor 325x219-1unit, Bend 90°-219-1unit, Bend 45°-159-1unit).	unit	8		
6	Non-destructive testing of Welded Joints				
6,1	X-Ray of D720 pipeline	km	10,603		
6,2	Double test of D720 pipeline with UT	unit	99		
6,3	X-Ray of D200 Pipeline	km	0,065		
6,4	X-Ray of D150 Pipeline	km	0,081		
6,5	Ultrasonic Test of D89 Pipeline	km	0,360		
7	Field Joint Coating				
7,1	Sandblasting of D1200 Casing pipes and coating with 3PE material	km	0,228		
7,2	Sandblasting of D700 welded joints and coating them with thermal sleeves	km	10,603		
7,3	Sandblasting of D200 welded joints and coating them with thermal sleeves	km	0,065		
7,4	Sandblasting of D150 welded joints and coating them with thermal sleeves	km	0,081		
7,5	Sandolasung of D89 welded joints and coating them with anticorrosive material	кт	0,360		
8	Road Crossings				
8,1	Installation of D1200 casing pipes to the design depth	m	66		
8,2	Arrangement of casing from wood and dielectric material around the D700 mm pipe	m	66		
8,3	Installing D/00 mm coated pipe section into the casing	m	66		
81	Installation of D1200 casing nines to the design denth	m	59		
8.5	Arrangement of casing from wood and dielectric material around the D700 mm nine	m	59		
8,6	Installing D700 mm coated pipe section into the casing	m	59		
,-					
8,7	Sealing ends of casing pipes with bitumen	unit	4		

8.8	Isolation of D50 pipe section (venting candel)	m	25		
8.9	Installation of D50 venting candel	unit	2		
0,0	instantation of Doo voltang candel	unit			
9	Railway crossing				
0.4	A		26		
9,1	Arrangement of casing from wood and dielectric material around the D1200 mm pipe	m	26		
9,2	Installing D1200 mm coated pipe section into the existing D1400mm casing		103		
9,3	Filling void between 1200 and 1400 mm casing pipes with concrete	m3	10,6		
9,4	Arrangement of casing from wood and dielectric material around the D/00 mm pipe	m	103		
9,5	Installing D700 mm coated pipe section into the casing	m	103		
9,6	Sealing ends of casing pipes with bitumen	с	2		
9,7	Isolation of D50 pipe section (venting candel)	m	10		
9,8	Installation of D50 venting candel	с	1		
10	Pine concreting, concrete slab arrangement and concrete	weights installati	on		
10	The concreting, concrete side arrangement and concrete	weights instantati	.011		
10,1	Installation of RC slabs on the WREP crossing (1.5×1×0,1m)	m2	150		
10,2	Installation of rock shield on D700 pipes and ballasting with R/C weight	m3	31		
10.3	Concrete coating of D700 pipes with R/C B25	m	291 30		
			291,50		
11	Pipe lowering with preliminary preparation of 10cm so	oft ground beddi	ng		
11,1	Preliminary preparation of 10cm sand bedding	km	10,749		
11,2	Lowering of D700 coated pipeline section	km	10,603		
11,3	Lowering of D200 coated pipeline section	km	0,065		
11,4	Lowering of D150 coated pipeline section	km	0,081		
11,5	Lowering of D89 coated pipeline section along with the D700 (same trench)	km	0,360		
40	Deal-filling with the local ground weather and the set of the set	d the nine and d	Dom chore 4	nino	
12	Backfilling with the local ground, preliminary padding with sand arroun	a the pipe and 2	ocm above the	<u>pipe</u>	
12,1	Preliminary padding with sand arround the pipe and 20cm above the pipe	km	10,749		
12,2	D700 trench backfill	km	10,603		
12.3	D200 trench backfill	km	0.065		
12.4	D150 trench backfill	km	0.081		
,.			0,001		
13	Cleaning and Testing of pipeline				
40.4		1	1 2227		
13,1	Pre-testing of pipeline sections on 8.1bar during 12hours	km	1,3337		
13,2	Pre-testing of pipeline sections on 6./5bar during 12hours	km	0,466		
13,3	Pre-testing of Valves	unit	2		
13,4	D700 pipeline section cleaning with brush and magnetic PIGs	km	10,603		
13,5	Testing of D700 pipeline section	km	10,603		
13,6	Dewatering of D700 pipeline section with Polly PIG	km	10,603		
14	Installation of Valves				
14	instantion of valves				
	Installation of D150 valve (NDT of welded joints, coating with 3 layer of under ground	•.			
14,1	parts and anticorrosion paining of above ground parts)	unit	1		
14.2	Installation of cold venting candle (D80 on venting candle)	unit	1		
14.3	Arrangement of D150 valve teritory fencing and graveling	unit	1		
,=	Installation of D200 valve (NDT of welded joints, coating with 3 layer of under ground	unit	-		
14,4	nastantidion of D200 value (1001 of weided Joints, couring with Shayer of under ground parts and anticorrosion naining of above ground narts)	unit	1		
14.5	Arrangement of D200 valve teritory fencing and graveling	unit	1		
1/ 6	Installation of lightning protection	unit	2		
14,0		um	2		
15	Anti-erosion activities				
	Installation of water drainage berms				
15.1	Soil processing for the arraignment of water diversion berm and lining it with rocks	unit	3		
,.	(drawing #NSGP002_GA00_PL_SCM_00021)		_		
	Installation of trench brakers		10		
15,2	Installation of trench brakers with sand-cement mixture bags(6:1)	Breaker	13		
15,3	Installation of pipes between the trench brakers	m	41		
	Din ran installation				
15 4	Surface leveling and arrangement of 0.2 m thick lever using 40.70 mm array	2	272		
15,4	Surface revening and arrangement of 0,5 m thick layer using 40-70 mm graver	mo	213		
15,5	Installation of rip rap with 0.8m diameter stones for 1 High	m3	790		
15.6	Surface leveling and arrangement of 0.15 m thick layer using 40-70 mm gravel	m3	36		
45.7	Installation of the new with 20kg random for 0.2 High		70		
15,7	Instantation of tip rap with 50kg focks for 0.3 High	m3	12		
	Gabions arrangement				
45.0	Surface leveling and among survey of 0.2 set this 1.1 second state 40.70 second		102		
15,8	Surface leveling and arrangement of 0,3 m thick layer using 40-70 mm gravel	m3	123		
15.9	Installation of Gabions (400x200x50cm) (filling with rocks 15cm)	unit	45		
15.10	Installation of rip rap with 30kg rocks for 0.4 High	m3	6		
-		-	-		

	Installation of geomats						
15.11	Installation of geomats and reinforcement with anchores	m2	685				
15.12	Top soil spreading and seeding on geomats	m2	650				
	Installatiom of channels						
15,13	Installation of I type Longitudinal channels	m	325,1				
15,14	Installation of II type Reinforced Concrete Longitudinal channels	m	1471,9				
15,15	Installation of I type diversion channels	unit	4				
	Arrangement of passages over the pipeline						
15,16	Arrangement of 20 cm thick sand foundation for type I passage on the design pipeline	m3	9				
15,17	Preparation of 5cm thick sand-cement mixture (9:1)	m3	2,25				
15,18	Installation of reinforced concrete slabs (200x150x20cm)	unit	15				
15,19	Arrangement of 20 cm thick sand foundation for type II passage on the design pipeline	m3	15,6				
15.20	Preparation of 5cm thick sand-cement mixture (9:1)	m3	3,9				
15,21	Installation of reinforced concrete slabs (200x150x20cm)	unit	26				
16	Cathodic protection						
	· · ·	1					
16,1	Installation of control metering units	unit	26				
16,2	Installation of F3K block for control metering unit	unit	17				
16,3	Installation of straps	unit	14				
16,4	Installation ПМ10-У protectors	unit	18				
17	Other activities						
17,1	Installation of dielectric material on oil (WREP) pipeline crossing	m2	75				
17,2	Installation of warning tape on oil pipeline crossing	m	40				
17,3	Installation of marker posts	unit	29				
17,4	Installation of marker posts: "Beware Pipeline, Parking is Restricted	unit	11				
17,5	Tie in to the existing line 150×150	unit	1				
17,6	Installation of D150 insulation joint (with welding edges)	unit	1				
17,7	Cost of vented gas	m3	67,51				
17,8	Tie in to the existing line 200×200	unit	1				
17,9	Installation of D200 insulation joint (with welding edges)	unit	1				
17.10	Cost of vented gas	m3	1531				
17.11	Ti in in existing pipeline (700x700)	unit	1				
17.12	Cost of vented gas	m3	94222				
17.13	Transportation and unloading of remaining pipes and other fittings to the Lilo PY	%	100				
17.14	Reinstatement in accordance with EMP	km	10,603				

Note: Bidder's cost estimate of pipeline construction should include costs of all those materials and devices that are considered by the construction project and are not provided by GOGC